



CITY OF JACKSONVILLE BEACH

INFORMATION FLYER



Project: A1A Water Main Replacement Project

This project will be replacing existing 2", 6" & 8" deteriorated water mains and water service lines located on the east & west side of A1A between 6th Ave. North & 20th Ave. North.

PROJECT OVERVIEW

- Work will commence on the east side of A1A starting from 6th Ave. North and continue in a northerly direction on a block-by-block basis. After all of the work on the east side of A1A is completed the crews will shift to the west side of A1A and start working from 20th Ave. North in a southerly direction.
- Temporary 2" water mains will be installed aboveground to continue providing water service to our customers.
- Existing concrete sidewalks & driveways will be removed.
- The water mains will be removed and replaced which includes flushing, testing, disinfecting, sampling prior to transferring water services.
- Restoration of concrete sidewalks, driveways and previous grassed areas.
- It is anticipated that it will take approximately two (2) weeks per block to complete the removal and replacement of the water mains.

ESTIMATED PROJECT SCHEDULE:

- **Start:** October 15, 2018
- **Complete:** October 16, 2019

? QUESTIONS ?

- **CITY PUBLIC WORKS Points-of-Contact:**
 - ◆ Keith Crumrine , Construction Coordinator
Phone: 904-226-4369 (Cell)
 - ◆ Dennis Dupries, Construction Manager,
Phone: 904-509-0268 (Cell)
- **CONTRACTOR Points-of-Contact:**
Maer Homes, LLC
 - ◆ Office: 904-329-3277
 - ◆ After Hours Contact:
 1. Jo Perez: 904-214-2776
 2. Steve Gonzalez: 904-219-2642
 3. Michael Gonzalez: 904-626-1487

PROJECT UPDATES:

Project updates are planned on a periodic basis as the construction work proceeds.

During the construction phase of this project, there may be times when your driveway is inaccessible or you will have limited access to the front of your home or business due to construction activities near your home / business. The contractor will make every effort to provide you access as soon as the crew has completed their installation in that area. At the end of each weekday, excavated areas will be filled and compacted and all residential and business driveways should be accessible. Our intent is to minimize any inconveniences to the local residents & businesses during this time and we ask for your patience as this project progresses. There will also be several short durations (1/2 to 1 hour) of scheduled water outages. A formal written or verbal notice will be given to you, by the Contractor, at least two (2) days prior to the scheduled outage. Unfortunately, due to condition of the water main and services being replaced there is the possibility that unscheduled water outages may occur that are beyond our control so we apologize in advance for any inconvenience that you may suffer.

Note on Landscaping and Irrigation

If you have landscape plants, trees, bushes, landscape timber, landscape block and/or other landscape type materials located within the City owned Avenue right-of-ways abutting A1A and within our project limits that you wish to save, we request you remove them or relocate them onto your property. Plants and/or landscape items left in the City right-of-way that are removed due to the construction activity will not be replaced by the contractor. The contractor will also be contacting property owners to identify any irrigation systems located within the construction areas. Any functioning irrigation systems damaged by our construction will be repaired by the contractor at no cost to the property owner. If you have any landscaping / irrigation questions, you can contact Jo Perez the foreman for Maer Homes, LLC.

3RD ST. N. (A1A) WATER MAIN IMPROVEMENTS



PROJECT AREA: 3rd St. N. (A1A) from 6th Ave. N. – Seagate Ave

PLANNED CONSTRUCTION START – October 12, 2018.

PROJECT DURATION – 365 days from notice to proceed.

- Improve available water pressure on both sides of A1A
- Working in Florida Department of Transportation (FDOT) Right of Way
- Replace old 2" galvanized pipes with new 4" PVC pipes
- Replace old 8" unlined cast iron pipes with new 8" PVC pipes
- Abandon / Grout fill pipes which cross 3rd St. N. at six locations